

Project: 187-M Gullberg-III

Communication Construction Services					
Sr.no	Description Of Item	Unit	Quantity	Unit Rate	Amount
A	Dismantling & Removal Works				
i	Ceiling Removal				
	Dismantling of existing ceiling including removal of frame shifting of debris outside the site limit stacking the usable material at site complete in all respect as directed by the Engineer/In Charge.				
	Drawing Room, Lobby, Dinning, Study, Bed Room F.F, Bath & Kitchen	Sft	1,500.00	95.00	142,500.00
B	New Works				
i	Lawn Pavers				
	Providing laying leveling & curing lawn pavers as per drawing work comprising of cleaning the existing surface, excavation P.C.C (1:2:4) as sub base laying of rock tiles/tuff pavers with cement sand mortar and gravel/crush filling in the grooves complete in all respect as per drawing or as directed by the architect.	Sft	275.00	1,283.00	352,825.00
ii	Marble on wall (Red travertine)				
	Providing, laying & fixing in position red travertine on wall work comprising of 3/4" thick travertine marble of any size up to 36" including cost of wall clumps labor filling and mortar filling on back side cleaning curing complete in all respect as per drawing or as directed by the Architect. (Base price of Marble 2500 per sft)	Sft	142.00	4,587.00	651,354.00
iii	Wall Moldings				
	Providing making joining & fixing in position wall molding comprising of solid Ash Wood minimum 4" wide, CNC cut design excluding the cost of polish cleaning and finishing complete in all respect as per drawing or as directed by the architect for the mentioned areas (Living, lobby, study, drawing, dinning bed room, kitchen , F.F lobby)	Rft	780.00	2,830.00	2,207,400.00
iii (a)	Polish for moldings	Rft	780.00	450.00	351,000.00

Project: 187-M Gullberg-III

Communication Construction Services					
iv	Wardrobe under stair				
	Providing making joining & fixing in position wardrobe comprising of Chip board boxes for storage, front shutter on double side veneered sheet 15mm and fluting panels of solid red oak as per drawing or as directed by the architect. But excluding the cost of polish	Sft	38.00	3,650.00	138,700.00
iv (a)	Polish for Wardrobe	Sft	105.00	450.00	47,250.00
v	Cable Duct (Wooden)				
	Providing making joining & fixing in position mdf boxes for cable cap including front shutter with MDF sheet 15mm as per drawing or as directed by the architect. But excluding the cost of paint	Job	1.00	18,500.00	18,500.00
vi	Wall Moldings (Lift Door)				
	Providing making joining & fixing in position wall molding comprising of solid Ash Wood minimum 4" wide, CNC cut design including cost of polish cleaning and finishing complete in all respect as per drawing or as directed by the architect.	Job	1.00	88,500.00	88,500.00
vii	Sofa Frame & Cabinet (Study Area)				
	Providing making joining & fixing in position wall cabinet with sofa frame as per design including with veneered sheet but excluding the cost of polish & sofa poshish cleaning and finishing complete in all respect as per drawing or as directed by the architect.	Sft	64.00	2,570.00	164,480.00
vii (a)	Polish for moldings	Sft	245.00	450.00	110,250.00
viii	Study Wardrobe jute cloth front				
	Providing making joining & fixing in position wardrobe comprising of Chip board boxes for storage, front shutter of solid red oak MDF & Jute Fabric as per drawing or as directed by the architect. But excluding the cost of polish	Sft	64.00	3,250.00	208,000.00
viii (a)	Polish for frame	Job	1.00	32,500.00	32,500.00

Project: 187-M Gullberg-III

Communication Construction Services					
ix	<u>Kitchen Cabinet (First Floor)</u>				
	Providing making joining & fixing in position wardrobe comprising of Chip board boxes for storage, front shutter of solid red oak MDF & Jute Fabric as per drawing or as directed by the architect. But excluding the cost of polish	Sft	24.00	4,650.00	111,600.00
ix (a)	<u>Polish for frame</u>	Job	1.00	32,500.00	32,500.00
x	<u>Kitchen Counter (Out Door)</u>				
	Providing & making kitchen counter out door counter size minimum 5' x 2' x 3' length width & height respectively with following material details				
	Sink Bowl Base price 30000				
	Sink mixer base price 25000				
	Black granite on top				
	Brick masonry & plaster work				
	Tiles under counter & walls				
	Sanitary pipes & water supply				
	Price with all above scope of work	Job	1.00	285,000.00	285,000.00
xi	<u>Paint Work (Internal)</u>				
	Providing and Applying of Internal Paint Work Plastic Emulsion three coats on walls (ICI, burger or equivalent) of approved color including, scraping rubbing, grinding, cleaning, filling and preparing the base etc. wall filling/putty (ICI, Berger, Nippon or equivalent and including cost of joint crack filler on M.D.F & False ceiling work.				
	Paint Work (Ceiling & Walls)	Sft	12,000.00	130.00	1,560,000.00
xii	<u>M.S Louver Door</u>				
	Providing , fabricating, welding & fixing in position M.S louver door comprising of M.S 16Swg Chowkhat, 18swg sheet louvers including cost of labor & fixing on site complete in all respect as per drawing or as directed by the Architect.	Sft	50.00	2,550.00	127,500.00
xii (a)	Deco paint for above door	Sft	135.00	450.00	60,750.00
xiii	<u>External Paint (Weather Shield)</u>				
	Providing and Applying of external Paint Work weather shield three coats on walls (ICI, burger or equivalent) of approved color including, scraping rubbing, grinding, cleaning, preparing the base etc. But excluding the cost of plaster repair works				
	External Weather shield	Sft	6,000.00	90.00	540,000.00

Project: 187-M Gullberg-III

Communication Construction Services					
xiv	Water Repellent				
	Supply & apply water repellent work comprising of cleaning the surface with wire brush and water letting dry and 1-coat of water repellent complete as per written instructions of manufacturer complete with labor folding & cleaning.				
	External Weather shield	Sft	2,000.00	120.00	240,000.00
xv	Eelctrical Works				
	Making any kind of minor changes hanging new lights, new switch plates, cable laying (All type of material cables, lights switch plates & fans will be provided by the owner)	Job	1.00	365,000.00	365,000.00
	Total				7,835,609.00